

BEFORE WE START

Our goal is to provide our clients with Best Work: Error-Free, On-Time, Every Time. We'll need a few things on site to make this happen.



POWER

- Single Phase 240V - 30/50 amp -OR- Three Phase 240V - 50/60 amp -OR- Three Phase 480V
- Whip-provided by DCD; 3-phase breaker by client
- 3-5 Dedicated 110V Outlets



WATER

- Access to water on site
- If needed, slurry removal.



LIGHTS

- Space has access to adequate lighting



HVAC

- Space has adequate airflow and humidity control for successful install



TRASH

- Access to dumpster on site.



BATHROOMS

- Site has bathrooms for Craftsmen.



PATCHING

- All known patching and repairs are accounted for in Proposal.
- Client is aware that additional patching will be discussed if needed.



EMPTY SPACE

- Non-permanent items removed from workspace
- Doors and trim have been removed or have not been installed.
- Area has been swept and scraped to remove large debris and excessive dirt.
- Exclusive access to workspace during install.
- Client is aware that additional patching will be discussed if needed.